

640 LF of new 8-inch PVC water pipeline on La Brea St to provide RMWD water service to:

- 4 parcels on private wells
- 2 parcels with spaghetti lines

430 LF of new 8" PVC water pipeline and a new pressure reducing station on Rotanzi St to improve fire flow capacity and to provide another water source

3,300 LF of new 8" PVC water pipeline on Kalbaugh St, Beverly St, and Haley St to provide RMWD water service to:


- 12 parcels on private wells
- 10 parcels with spaghetti lines

Source: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, US

**DRAFT**

**Legend**

- Proposed Hydrant
- Existing Hydrant
- RMWD Water Line
- Proposed Water Line



**NV5**

15092 AVENUE OF SCIENCE, SUITE 200  
 SAN DIEGO, CA 92128  
 P: 858.385.0500 WWW.NV5.COM

**RAMONA ACRES CONSOLIDATION - PHASE 1 FEASIBILITY STUDY**  
**RECOMMENDED PROJECT**

DATE SUBMITTED: AUG 2022

EXHIBIT  
**1**

SCALE  
 1 inch = 300 feet

JOB NUMBER  
 227522-0001354.01